



PROJECT TYPE: SURFACE PREPARATION AND DIAMOND DRILLING

DURATION: 6 DAYS

SUMMARY: WAREHOUSE REFURBISHMENT INVOLVING DIAMOND DRILLING, GRINDING AND CAPTIVE SHOT BLASTING.

Holemasters Scotland Limited has just completed a warehouse floor refurbishment for Prime Build solutions Ltd in Cambuslang Glasgow.

The initial works took place over 4 days and consisted of over coring and removal of 445 bolts. These bolts were left from the previous tenants racking system. Also included was 25m² of edge grinding prior to the client carry out the necessary resin repairs to the floor.

A return visit to carry out the remaining works was programmed for a week later to ensure the repairs had sufficient time to cure and other trades operating MEWPS on the floor had completed their works packages.



With a return rate of 1200m² a day a further 2 days was taken to Captive Shot Blast 1650m² to clean and texture the surface and grind down the resin repairs flush prior to the clients application of a new paint coating.

For more information please call 0845 467 1500

or

visit the website www.holemasters-scotland.co.uk

